

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT		1. CONTRACT ID CODE		PAGE OF PAGES 1 6	
2. AMENDMENT/MODIFICATION NO. A001		3. EFFECTIVE DATE September 19, 2009		4. REQUISITION/PURCHASE REQ. NO.	
5. PROJECT NO. (If applicable)		6. ISSUED BY Carolee Cooper, Contracting Officer U.S. Embassy Panama 783 Bldg. Clayton, Panama Phone (507) 207-7399		7. ADMINISTERED BY (If other than Item 6) CODE	
8. NAME AND ADDRESS OF CONTRACTOR (NO., street, city, county, State, and ZIP Code)		9a. AMENDMENT OF SOLICITATION NO. X SPM070-09-Q-0044		9b. DATED (SEE ITEM 11) September 8, 2009	
		10a. MODIFICATION OF CONTRACT/ORDER NO.		10b. DATED (SEE ITEM 13)	
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS					
<p>[X] The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers [X] is extended, [] is not extended</p> <p>Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning <u>1</u> copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.</p>					
12. ACCOUNTING AND APPROPRIATION DATA (If required)					
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.					
A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.					
B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b)					
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:					
D. OTHER (Specify type of modification and authority)					
E. IMPORTANT: Contractor [] is not, [] is required to sign this document and return _____ copies to the issuing office.					
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)					
The purpose of this amendment is to make two (3) revisions in the solicitation and to extend the closing date. Reference Block 11 on receipt acknowledgement.					
The closing date is extended until Wednesday, September 23, 2009 at 11:00am local time.					
SEE NEXT PAGE.					
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.					
15A. NAME AND TITLE OF SIGNER (Type or print)			16A. NAME OF CONTRACTING OFFICER Carolee Cooper, Contracting Officer		
15B. NAME OF CONTRACTOR/OFFEROR BY _____ (Signature of person authorized to sign)		15C. DATE SIGNED	16B. UNITED STATES OF AMERICA BY  (Signature of Contracting Officer)		16C. DATE SIGNED 9-16-2009

- A. Attachment # 1 Specifications is revised. Please delete and replace with attached Attachment #1.
- B. Section G.7, SPECIAL WARRANTIES, is revised, please delete paragraph two and replace with:

The installation of all civil works will be guaranteed during a *one-year* from the date of the final acceptance by the U.S. Government.

- C. Attachment #2 Breakdown of prices is revised. Please delete and replace with attached Attachment #2.

ATTACHMENT # 1 - SPECIFICATIONS

SCOPE OF WORK PROVIDE STEEL STRUCTURE ROOF TO THE BASKET BALL COURT AT THE NEW EMBASSY COMPOUND

**LOCATED AT 783, DEMETRIO B. LAKAS AVENUE, CLAYTON
REPUBLIC OF PANAMA**

1. GENERAL INFORMATION:

The Embassy of the United States of America requires professional services and prospective contractors to submit a quotation to construct a steel structure roof to the basketball court in the NEC.

2. PROJECT REQUIREMENTS:

Description of Project: The new basketball court roof shall be a rigid steel frames structure measuring 34.75 meters long by 21.35 meters wide by 7.50 meters high.

Existing Condition: There is a basketball court built in accordance with the Basketball Layout Detail as outlined in this SOW.

3. GENERAL REQUIREMENTS:

Under this SOW, the Contractor shall provide a steel structure roof to the NEC basketball court. The work shall include design and construction drawings, foundations, WF frame columns and beams, purlings, thermal insulation and prefinished sheet metal roof panels. All ferrous metal surfaces shall be painted with two coats of primer and two coats of champagne bronze finish. The Contractor shall provide As-Built drawings for this project.

4. SCOPE OF WORK:

The Embassy of the United States of America invites prospective offeror to submit a quotation with a breakdown of proposal prices for the following work.

Contractor shall provide:

- 4.1 Earthwork. Twelve (12) excavations for foundations.
- 4.2 Construction of twelve (12) footings and pedestals for steel frame columns.
- 4.3 Erection of rigid steel frames combining columns and a beam or girder welded together to make a rigid connection.
- 4.4 Installation of cold formed 2" x 8" type C purling, U.S. Gauge 16.
- 4.5 Installation of wire mesh to support thermal insulation with thermal resistance R10 or higher.

- 4.6 Installation of LOW E thermal insulation with U-Factor = 10 or higher.
- 4.7 Installation of prefinished galvanized sheet metal roof panels U.S. Gauge 24.
- 4.8 Painting of all ferrous metal surfaces with two coats of primer and two coats of champagne bronze finish.
- 4.9 **Provide a complete set of "as-built" drawings.**
- 4.10 Provide two 34.75 meters long gutters along both slopes, and two downspouts. One downspout will discharge heading to a south side open concrete channel, and the other heading to a northwest storm drain manhole. Gutters and downspouts cross sectional areas will be calculated based on the local rainfall data and roof area.
- 4.11 Fix the cracks and re-paint. Surface preparation requires to remove the old epoxy paint completely to the bare concrete to ensure adherence of new non-skid sport/athletic paint (acrylic latex of high resistance) for sport concrete courts. Finish shall be an acrylic latex paint specially formulated for a flat finish and protection of sport concrete courts, and for interior and exterior use. Paint shall have high resistance to abrasion. Court shall be forest green color, goal areas and circles shall be red color, and playing lines shall be 2-inch wide white color.
- 4.12 Remove of construction and installation debris from the area daily, and before final acceptance of the work.

5. WARRANTY:

The installation of civil works will be guaranteed during a *one-year* period from the date of the final acceptance by the U.S. Government.

6. CONTRACTOR INCLUSIONS:

- 6.1 Contractor will provide all labor, expendable materials, tools and equipment to perform a complete job.
- 6.2 Contractor will provide existing site landscape protection from barrier site construction.
- 6.3 Contractor will provide cold water for employees while on site. Contractor will remove all unused construction materials from site and dispose of properly daily.
- 6.4 Contractor will provide all work trash containers and remove from site.
- 6.5 Contractor will provide a Performance Work Schedule in the form of a "bar chart" with his proposal, which will include number of working days from start to completion date.
- 6.6 Contractor will remove all trash from site associated with work daily.
- 6.7 Contractor work will be performed Monday through Friday from 8:00 a.m. until 5:00 p.m.
- 6.8 Contractor will provide number of construction personnel to perform work in proposal.
- 6.9 Contractor will provide an onsite quality control supervisor/foreman to direct contractor personnel.
- 6.10 Contractor will provide written proof of health insurance of all onsite contractors' employees working.
- 6.11 Contractor will provide a first aid kit for their employees on site.

- 6.12 USG facilities personnel will escort contractor's employees.
- 6.13 Contractor will provide name and cédula numbers of all contract employees three working days prior to start of work. Provide all vehicle license plate numbers that are required to enter site-requiring clearance in advance.

7. CONTRACTOR EXCLUSIONS:

- 7.1 Any additional work other than specified.
- 7.2 Cross-link fence.
- 7.3 Demolitions.
- 7.4 Retaining walls.
- 7.5 Stairs.
- 7.6 Concrete pavement.

8. RELATED DOCUMENTS:

7.7 Contract Drawing and Details

- 7.7.1 Basketball Layout Detail
- 7.7.2 South Elevation
- 7.7.3 Foundation, Footing and Pedestal Detail

7.8 Contract Reference Specifications

- 7.8.1 Section 03300 – Cast-In-Place Concrete
- 7.8.2 Section 05120 –Structural Steel
- 7.8.3 Section 07411 – Metal Roof Panels
- 7.8.4 Section 09912 – Painting



**ATTACHMENT #2 - PRICE PROPOSAL FORMAT
BREAKDOWN OF PROPOSAL PRICE BY DIVISIONS OF SPECIFICATIONS**

DETAIL	QTY.	UNIT	LABOR	MATERIALS	TOTAL COST
CLIN 001 Earthwork. Twelve (12) excavations for foundations.	1	job			
CLIN 002 Construction of twelve (12) footings and pedestals for steel frame columns.	1	job			
CLIN 003 Erection of rigid steel frames combining columns and a beam or girder welded together to make a rigid connection.	1	job			
CLIN 004 Installation of cold formed 2" x 8" type C purling, U.S. Gauge 16.	1	job			
CLIN 005 Installation of wire mesh to support thermal insulation with thermal resistance R10 or higher.	1	job			
CLIN 006 Installation of LOW E thermal insulation with U-Factor = 10 or higher.	1	job			
CLIN 007 Installation of prefinished galvanized sheet metal roof panels U.S. Gauge 24.	1	job			
CLIN 008 Painting of all ferrous metal surfaces with two coats of primer and two coats of champagne bronze finish.	1	job			
CLIN 009 Provide a complete set of "as-built" drawings.	1	job			
CLIN 010 Provide two 34.75 meters long gutters along both slopes, and two downspouts. One downspout will discharge heading to a south side open concrete channel, and the other heading to a north east storm drain manhole. Gutters and downspouts cross sectional areas will be calculated based on the local rainfall data and roof area.	1	job			
CLIN 011 Fix the cracks and re-paint. Surface preparation requires to remove the old epoxy paint completely to the bare concrete to ensure adherence of new non-skid sport/athletic paint (acrylic latex of high resistance) for sport concrete courts. Finish shall be an acrylic latex paint specially formulated for a flat finish and protection of sport concrete courts, and for interior and exterior use. Paint shall have high resistance to abrasion. Court shall be forest green color, goal areas and circles shall be red color, and playing lines shall be 2-inch wide white color.	1	job			
CLIN 012 Remove of construction and installation debris from the area daily, and before final acceptance of the work.	1	job			
A Other (If Required)	1	job			
B	1	job			
TOTAL COST OF PROJECT:					